



SERVICE BULLETIN 233
ISSUED: 08/01/2025

Mandatory SFCII-30 Blade Brake Spring Replacement

SUBJECT: Replace 487296 spring to 488561 spring.

SITUATION: It has come to our attention that some 487296 may not meet the engineered spring requirements. This can lead to the clutch brake not disengaging fully, resulting in premature clutch wear.

SOLUTION: To ensure optimal performance and customer satisfaction we advise that all SFCII-30 units within the serial number range listed below have the stock 487296 spring replaced with 488561 spring.

UNITS

AFFECTED: Machines with a serial number within the following range:

Model
SFCII-30-7CV-S

Serial Range
Y3300001 - Y3300962

REQUIRED: One (1) 488561 spring.

WARRANTY: Use Failure Code X4-173
.5 hrs labor